8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Approximate estimate of quantities for constructing a building for the Anglo-Vernacular School at Bowringpet.

No.	Items of work	Unit	Quantity
1	Earthwork excavation and filling basement	C. yd.	176
2	Concrete filling foundation	C. ft.	1,599
3	Burnt stone in chunam for foundation and basement...	„	4,025
4	Burnt brick in clay superstructure	„	4,683
5	Burnt brick in chunam	„	1,276
6	Arch work	„	196
7	Burnt stone slabs roughly dressed	S. ft.	745
8	Chunam plastering	Sqr.	89·89
9	White and colourwashing	„	89·89
10	Teakwood wrought and put up with wood oiling	C.ft.	157·36
11	Roofing with 1st Mangalore tiles over teak reepers	Sqr.	21·84
12	Ridge tiles set in mortar	R. ft.	126
13	Teakwood battened door with hinges	S. ft.	252
14	Teakwood battened windows with iron bars	„	288
15	Teakwood ventilators with glazed shutters, iron works, etc., complete ...	„	81
16	Teakwood circular ventilators	„	28
17	Chocolate painting	Sqr.	12·99
18	Terracing over verandah	„	3·00
19	Chunam pointing for basement	„	3·33
20	Finials, large	No.	4
21	Line sheet for valleys	S. ft.	156
22	Flooring with Cuddapah slabs over 3" concrete and cement pointing ...	Sqr.	17·71
23	Cornice for gables roof and verandah	R. ft.	338
24	Moulding cornice (3"×3")	„	306
25	Chunam borders	„	84
26	Parapet wall	„	60
27	Wire fixing of strand	„	10,4,0
28	Supplying bolts with nuts 1 foot long	No.	40
29	Burnt stone slabs with drilling holes, dressing and fixing, etc., complete ...	S. ft.	312
30	Corner posts with fixing (8'×9"×9")	No.	8
31	Honney wood gates with pillars iron works, fittings, etc., complete... ...	„	2
32	Teakwood planks 1" for valleys	S. ft.	52

V. V. KARVE,
Executive Engineer.

TUMKUR DIVISION.

Notification.

Attention is invited to notification published in detail *vide* pages 105—106, Part IV of *Mysore Gazette*, dated 31st January 1918, calling for tenders for restoring Bettahalli Minor Tank of Huliyurdurga hobli in Kunigal Taluk. The later date for tender is 25th February 1918.

Notification.

Attention is invited to notification published in detail *vide* pages 106—107, Part IV of *Mysore Gazette*, dated 31st January 1918, calling for tenders for constructing special wards and kitchen in the Civil Hospital at Tumkur. The later date for tender is 20th February 1918.

Dated 4th February 1918.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Tumkur Division, up to 28th February 1918, for improving and extending A.-V. School at Kunigal An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1919.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Tumkur Division, except Sundays and General holidays, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of rupees three hundred and fifty only in cash or Government Promissory Notes as earnest money, and be superscribed "Tender for improving and extending A.-V. School at Kunigal," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Abstract estimate showing the quantities for improving and extending the Anglo-Vernacular School at Kunigal.

No.	Items of work	Per	Quantity
1	Earthwork excavation and filling in basement	C. yd.	85
2	Burnt stone in mortar	C. ft.	613
3	Burnt brick in chunam	"	2,888
4	Arch work	"	118
5	Cut stone pillars with base and capitals	Each	16
6	Burnt stone slabs, dressed	S. ft.	545
7	Chunam plastering	Sq.	44·00
8	White and colour washing	"	110·00
9	Chunam pointing	"	2·65
10	Teakwood work wrought and put up with wood oiling	C. ft.	200·00
11	Roofing with 1st class Mangalore tiles on teak reepers	Sq.	26·00
12	Ridge tiles set in mortar	R. ft.	147
13	Cornic 9" thick	"	160
14	Zinc sheet for the valley with teak planks underneath	S. ft.	252
15	Teakwood doors panelled outer dimension	"	180
16	Teakwood windows outside panelled and inside glazed with iron bars, etc., complete	"	216
17	Glazed circular ventilators	"	14
18	Painting with silicate chacolate colour	Sqr.	23·00
19	Masonry finials	Each	6
20	Ventilating tiles	"	40
21	Teakwood sunshades	"	8
22	Removing windows marked A in hall and fixing new doors	"	2
23	Dismantling walls and fixing windows	"	4
24	Teakwood eave board 9" wide with wood oiling	R. ft.	140
25	Teak finials	Each	4
26	Teak terminals	"	8
27	Thin cornice over windows	R. ft.	292
28	Ornamental parapet wall	"	132
29	Flooring with Cuddapah slab over 3" concrete and cement pointing	Sq.	15·60
30	Dismantling and removing porch	Each	2
31	Unforeseen jobs if found necessary during execution	Lump sum	
32	Clearing site and levelling ground all round the school	"	
33	Gravelling ground around the school 7 yards wide	C. yd.	132
34	Stone brackets including fixing	No.	12

N. G. KRISHNA IYENGAR,
Offg. Executive Engineer.

MYSORE HEAD QUARTER RANGE.

Notice is hereby given that sealed tenders will be received at the office of the Assistant Engineer, Head Quarter Range, Mysore, up to 5 P.M. on the 5th March 1918, for dismantling the Band Room and constructing a new Car Shed at the South Gate of Fort, Mysore.

An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed in about six months after commencement.

2. The plans, detailed estimates and specifications may be seen at the office of the Assistant Engineer, Head Quarter Range, Mysore, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted in the prescribed printed forms which may be obtained from the Assistant Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items will be executed.

4. Indefinite remarks against item such "as per estimate" "as per data", etc., will not be considered.

5. Each tender must be accompanied by a deposit of Rs. 500 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tenders for dismantling the Band Room and constructing a new Car Shed at the South Gate of Fort, Mysore," as the case may be, and in default of which, tenders will be rejected.

6. The final acceptance of any tender will rest with the Chief Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

7. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

8. The name of the successful competitor, will be posted on the notice board in the Assistant Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.